9300 WIRE DRAG

9300 WIRE DRAG

AREA-4 Chiris 411-1007 11300-1117 11332-1280 11240-1114 Diag. Cht. Nos. 116-3, 1117 & 1280.

FORM C&GS-504

U.S. DEPARTMENT OF COMMERCE
ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION
COAST AND GEODETIC SURVEY

DESCRIPTIVE REPORT

Type of Survey WIRE DRAG R/H 40-2-73 #H 9300 WD
Field No.: 40-2-72 #H 9341 WD Field No.: #H9242 WD
LOCALITY
State TEXAS
General locality GULF OF MEXICO SAFETY FAIRWAYS Locality GALVESTON
19.73
CHIEF OF PARTY
CDR LEONARD E. PICKENS

LIBRARY & ARCHIVES

May 15, 1978

DATE

USCOMM-DC 37022-P66

Only H-9300 has 6

FORM	C&GS-537

U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION COAST AND GEODETIC SURVEY

REGISTER NO.

R/H 40-2-73 - #H9300WD 40-2-72 - #H9341WD 40-3-72 - #H9342WD

HYDROGRAPHIC TITLE SHEET


INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.

FIELD NO. R/H 40-2-73 R/H/40-2-72 R/H 40-3-72

State TEXAS
General locality GULF OF MEXICO - SAFETY FAIRWAYS
Locality GALVESTON
Scale 1-40,000 Date of survey 11 JUNE, 1973 - 22 June 1973
Instructions dated 26 JAN., 1973 Project No. OPR - 479
Vessel NOAA SHIPS RUDE & HECK
Chief of party CDR LEONARD E. PICKENS
Surveyed by SHIPS PERSONNEL
Soundings taken by echo sounder, hand lead, **postex
Graphic record scaled by
Graphic record checked by
Protracted by Automated plot by
Soundings penciled by
Soundings in fathoms feet at MLW XXXXXX BASED ON PREDICTED TIDES
HDEG Cat. 1 Survey
REMARKS: Verification to survey H-9300 w.D. was limited, no further processing is
Planned, reference should be made to the attached Verifier's Report/
Addendum for data on limitations, modifications, corrections,
and recommendations. This report portains to H-9300WD only.
Appid to Stids, 5-19-78 WOT

TABLE OF CONTENTS

- I. SHEET LAYOUT
- II. PROGRESS SKETCH
- III. A) AUTHORITY
 - B) CHARACTER & LIMITS OF THE WORK
 - C) CONTROL & LHORELINE
 - D) DATE OF SURVEY
 - E) TIDAL REDUCERS
 - F) JUNCTIONS
 - G) SPLITS
 - H) GROUNDINGS & HANGS
 - I) GENERAL NOTES
 - J) CURRENTS
 - K) DISCREPANCIES & COMPARISONS WITH RECENT SURVEYS & CHARTS
 - L) EQUIPMENT
 - M) MISCELLANEOUS
 - N) SUMMARY
 - D) RECOMMENDATIONS
 - P) APPROVAL
- IV. LIST OF ATTACHMENTS



430

94,00

PROGRESS SKETCH

0PR-479-R/H-73

WIRE DRAG: SHEET 40-2-73

GULF OF MEXICO

NOAA SHIPS RUDE & HECK

L.E. PICKENS, CHIEF OF PARTY

SCALE 1:460,732

JUNE 1973

REPRESENTS AREA COMPLETED
SHEET 40-2-73 H-9300 WD
STATISTICS LNM SNM
23.95 29.60

A. AUTHORITY

The authority for this survey was Project Instructions OPR 479-RU/HE-73 Safety Fairways, Gulf of Mexico dated 26 January, 1973. Investigation of a reported grounding was added to the instructions via radio message received on 5 June, 1973. (See enclosed copy under Project Instructions.)

CHARACTER AND LIMITS OF WORK

The purpose of the survey was to prove or disprove the existence of underwater hazzards to navigation in the Safety Approach Fairways to Galveston Bay, to investigate a reported obstruction near the tip of the Galveston South jetty, and to investigate a reported grounding west of the Southeast Fairway.

The boat sheet layouts were:

Sheet 40-2-73 LAT. 28041'30"N to 29004'00"N LONG. 93938'40"W to 94913'30"W

Sheet 40-3-72 LAT. 28°59'30"N to 29°27'30"N H-9342

LONG. 94000'00"W to 94025'50"W

Sheet 40-2-72 LAT. 28°31'30"N to 29°01'00"N

4-9341

LONG. 94°11'10"W to 94°36'50"W

The entire survey was done on a 1:40,000 scale.

C. CONTROL AND SHORELINE

Raydist DR-S Range-Range Control was used during all the fairway operations; the frequency was 3300.4 KHz resulting in a lane width of 45.39904 meters. No shoreline existed on any boatsheet.

One drag was done south of Galveston's South jetty to locate a reported

obstruction; combined electronic - visual control was used. (Not on N-9300)

The "Green" Raydist station was "MOORE" located in south Galvestion, and
the "Red" station was "HANT", approximately 50 miles northeast of
Galveston. Upon completion of operations "HANT" became the sight of the
"Green" station and the "Red" station was moved to the Sabine Pass area;
both stations are recoverable. A listing of all signals used is given in
Attachment I.

D. DATE OF SURVEY

Operations began on OPR 479, Galveston, Sheet 40-2-73 on 11 June and terminated on 22 June. Work on boat sheet 40-3-72 began on 25 June and ended on 11 July, 1973; work on sheet 40-2-72 began on 10 July and terminated on 11 July, 1973.

E. TIDE REDUCERS

The preliminary reduction of each days data was based on predicted tides; the actual tide data will be supplied by the Rockville office based on the tide gauge at the Galveston Pleasure pier.

F. JUNCTIONS

All sheets junction satisfactorily. H-9342 WD. (1973) joins H-9300 W.D. on the North Was

G. SPLITS

No splits exist. on M-9300 W.D.

H. GROUNDINGS AND HANGS.

Occassionally the wire was deliberately set out aground and towed off the shoal areas; these areas were later covered by another drag. No significant

Lan H-9300 WD

groundings were observed. Only one hang was encountered: I-beam near the Galveston South jetty. Divers buoyed the obstruction so the Corps of Engineers could remove it immediately.

Location: 29019108"N - 94041148"W

Effective depth: 20'

GENERAL NOTES I.

Morning and evening calibrations were done by steering range #2 and observing left angle to the Galveston South Jetty Light. Numerous lane checks were taken at various navigational buoys.

Towlines of 800 ft. and 1000 ft. were used the majority of the time thus putting the end buoys 265m and 326m respectively from the Raydist antennae. One exception exists; due to a weakened section of wire, the end vessel's towline during the drag on E-day (Sheet 40-3-72) was 235m long. For plotting purposes it was considered to be the standard 265m length. The shortened towline apparently increased the strain on the ground wire sufficiently to cause excessive lift in the end section (11-F). Because of the lift and because that section fell in an area of excessive overlap, it was rejected throughout the entire strip. The elimination of the section 11-F still left the strip with more than the specified 600 ft. overlap.

On C day (Sheet 40-2-72), strip 1, section 7-8 was only 900' long rather than the usual 1000'.

A small drag was done to hang a reported obstruction 0.6NM and bearing 329° to the Galveston South Jetty Light. The control was combined Raydist and visual. An I-beam was located and then buoyed by divers for future

















reference. Three point visual fixes were taken to establish the charted position, and the appropriate agencies and departments were notified. This unofficial drag was not recorded because the Corps of Engineers planned immediate removal of the I-beam. See Corps of Engineers Report on Holing of Dredge McKenzie in Attachment VI.

J. CURRENTS

Generally the current was from the NNW in the morning and rotated clock-wise through ENE by evening. Occasionally a west to east current was encountered. Current tests were taken before the majority of drags by tracking a float connected to a vaned drogue suspended at the depth of the anticipated drag. Velocities were consistently less than 1 knot.

K. DISCREPANCIES WITH CHARTS — See the attached Verifier's Report Addandum

Charted depths over the flat bottomed areas was found to be accurate; the shoal areas were often 1 to 1 1/2 ft. shoaler than charted. Wire dragging of shoal areas was preceded by ship Reconnaissance Hydrography. Not included with the survey records.

L. EQUIPMENT

The RUDE acted as Guide vessel; the HECK as End vessel. The launches and skiffs were used as tenders. Ship Hydrography was done with Raytheon (See Metrin K Abuc)

DE-723 fathometers. Standard wire drag equipment was utilized throughout the survey.

M. MISCELLANEOUS

Early in June daily thundershowers resulted in tenuous Raydist transmission; frequent lane checks at navigational buoys were necessary to insure the desired accuracy. Numerous launch and skiff breakdowns hampered progress. Leaky hydraulic lines to the drag winches of both ships caused minor delays. A one week in-port period was observed in late June for repairs and maintenance.

N. SUMMARY

not on H-9300

An obstruction was located at 29°19'08"N Latitude, 94°41'48"W Longitude with an effective depth of 20 ft. The Army Corps of Engineers planned immediate removal.

A reported 37 ft. shoal at $29^{\circ}03'56"N$ Latitude, $94^{\circ}18'04"W$ Longitude was cleared to a depth of 41 ft. — Not on N-9300

The safety fairways have been cleared at various depths to the 10 fathom curve.

O. RECOMMENDATIONS

Neither the obstruction near the Galveston South Jetty nor the reported 37 foot shoal area are recommended for charting. Not $\alpha_{\rm gel}({\rm cabla}$ to 4-9300



P. APPROVAL SHEET

All records of this survey prior to smooth plotting are hereby approved. The field work was personally supervised by the undersigned and the boatsheet and records were inspected daily. The survey is considered complete and adequate for charting.

LE Pickers

Commanding Officer

NOAA Ships RUDE & HECK

LIST OF ATTACHMENTS

- 1.. A) RAYDIST CONTROL STATIONS
 - B) VISUAL CONTROL SIGNALS
- II. LIST OF GROUNDINGS & HANGS
- III. A) DAILY RAYDIST CORRECTORS
 - B) ELECTRONIC CALIBRATION INFORMATION
- IV. STATISTICS
- V. AIDS TO NAVIGATION
- VI. PROJECT INSTRUCTION
 - A) CHANGE #1
 - B) CHANGE #2
 - C) CHANGE #3
- VII. RAYDIST STATION DESCRIPTIONS
- VIII. A) TIDES, SMOOTH (NOT-RECEIVED FROM ROCKVILLE)
 - B) REPORT, TIDE STATION
- IX. BOAT SHEET & ELECTRONIC CONTROL PARAMETER SHEETS

ATTACHMENT I

A. RAYDIST CONTROL STATIONS

 STATION
 LAT.
 LONG.
 REMARKS

 MOORE 1971
 29°14'03.520"N
 94°52'54.136"W
 Green

 HANT 1973
 29°40'03.0909"N
 94°04'20.73.56"W
 Red

B. VISUAL CONTROL STATIONS

CALIBRATION RANGE #1

SIGNAL

Texas City Cut A

Outer Rr. Range Lt. 29°19'55.804"N 94°44'45.322"W Front Range

Bolivar Pt. Lighthouse 29°21'59.597"N 94°46'00.263"W Rear Range

Galveston South Jetty Lt. 29°19'39.258"N 94°41'32.887"W Right Obj.

LAT.

LONG.

REMARKS

CALIBRATION RANGE #2

SIGNAL LAT. LONG. REMARKS Rear Range 29°22'18.334"N 94044'53.326"W Galveston Bay Ent. Ch. Rear Gal. Bay Front Range Ent. Ch. Front 29021'16.821"N 94°42'56.635"W Gal. South 94⁰41'32.887"W Left Object 29019'39.258"N Jetty Lt.

ATTACHMENT II

LIST OF GROUNDINGS AND HANGS

1
4
(B
o_{i}
Appendix I
<u>e</u>
K.
7
.e,
of the Verifiers
70
₹.
وق
a-
Óz
Ž
1
Addendum
2
2
in
2

POSITION				Grounded Cleared	Cleared	Cleared		
\$	Bouy	***		Effective by Day &	ve by Day & Effect	Effective Charted	Charted	Remarks
						:		
		29019'08"N 94041'48"W	94°41'48"W	20'				Unofficial drag
								Corps of Engineers planned immediate removal of I-beam that was found.
•		29°03'56"N	29°03'56"N 94°18'04"W	37'	£3	41*	421	Reported grounding 37' depth

ATTACHMENT III A.
DAILY RAYDIST CORRECTORS

SHEET #	DATE	DAY LETTER	VOL. NO.	RED CORR.R	UDE GREEN CORR.	RED CORR.H	EGREEN CORR.
40-2-73	11 June, 73	A	I	-0.2	+0.3	+0.1	-0.2
	18 June, 73	В .	I	+0.1	-0.4	0.0	0.0
0	19 June, 73	С	I	+0,1	-0.4	0.0	0.0 300
.930	19 June, 73	Ď	I	+0.1	-0.4	0.0	0.0 %
Ž.	21 June, 73	E	· I	+0.2	+1.0	+0.2	+1.6
	22 June, 73	F	II	+0.2	+1.0	+0.2	+1.6
40-3-72	25 June, 73	В	I	+0.2	-0.4	+0.3	+0.2
	26 June, 73	С	I		ANCHORE	D OUT,	
	27 June, 73	D D	I		NO CALI	BRATION	
	28 June, 73	E E	I & II	+0.2	-0.3	+0.3	+0.4
	11 July, 73	F F	II	+0.1	-2. 0	-0.1	-0.1
40-2-72	10 July, 73	В	I & I HYDRO	-0. 1	0.0	-0.7	+0.2
	11 July, 73	s c '	I	+0,1	-2.0	-0.1	-0.1

ATTACHMENT IV SHEET STATISTICS

DATE	DAY LETTER	STRIP NO.	VOL. NO.	POSITIONS	L.N.M.	S.N.M.
SHEET 40-2-73 H	- <i>9300</i>			·		
11 June, 73	Α	1 .	I	1-4	REJE	CTED
Ħ	A	2	I	5-20	2.80	3.36
18 June, 73	В	,1	ī	1-13	1.70	2.04
19 June, 73	С	1	I	6-23	2.50	3.50
20 June, 73	ם	1	I	5-36	5,55	6.94
. 11	מ	2	I	37-52	2.75	3.85
21 June, 73	E	, 1	. I	1-12	2.20	2.56
π .	Ε	2	I	13-28	3,10	4.34
22 June, 73	F	_ 1	II	1-10	2.15	1.83
ti .	F	2	II	11-17	1.20	1.08
SHEET 40-3-72 №	9342					
25 June, 73	В	1	I	1-31	5.36	7.24
26 June, 73	C	1	I	1-31	5.36	7.24
n	С	2 .	I	35-47 1/	2 2.55	3.44
27 June, 73	D .	1	1	1–26	5.02	6.22
11	מ	2	1.	27–39	2.76	4.17
Ħ	ם	3	I	40-54	2.33	3.19
28 June, 73	E	1	1 & 11	1-22	4.50	6.75
11 July, 73	F	1	II	1-11	1.70	2.15











ATTACHMENT IV CONT'D

DATE	DAY LETTER	STRIP NO.	VOL. NO.	POSITIONS	L.N.M.	S.N.M.	
SHEET 40-2-72 /	1-9341						
10 July, 73	В	*		1-31			
n	В	1	I	1-16	3,20	6.08	
11 July, 73	C	1	I	1-14	3.12	3.59	

^{*} Hydrography







ATTACHMENT V

AIDS TO NAVIGATION

No aids to Nov. on H-9300

NAME	LAT.	LONG.	REMARKS
R "2"	29°05'00"N	94013142#W	Used to check lane count
FIG 6s	28958 12"N	94°18'42"W	n
HU-HI	29°06'24"N	94°23'48"W	. н















Note —
Smooth Tides for all 3 surveys
(H-9300 WD, H-9341 WD, H-9342 WD) were
computed using a time difference of
-1.4 hours which is an average of
the four zoning areas. This is
considered satisfactory due to the
height of MHW above datum being
only 2.1 feet and the interval
required for wire Drag surveys being
0.5 feet.

CAM22 8/6/7						
			tic Marine C	enter D	ATE:	1. 1075
	TN: CAM2					
FR	$ROM: \frac{N}{N}$	128 d Hee	Č			
su	BJECT: Requ	est for Smoo	oth Tide Cor	rectors		
1.	Enclosed is	the logged	hourly heigh	nts tape for	the period	,, 1
	Property 10	· (1	rom Form 362	2, Hourly He	eights at Tid	le Station
		lace)		° (pc	A contract of the contract of	• •
	Tidal datum					
-	TIGAT GACUM	ть	(fee	et/fathoms b	elow MLW/MLI	W.
2.	Tidal differ	cences and c	ther constar	its for	47941	
			ong:o		(place	.).
		(positio	on)			
	(Hour,	ME Minute)	HEI	GHT et)	HEIGHT	RATIO licable)
			High Water		High Water	
						Don Hatel
				0	1	
•						
3.	Tidal differ	ences and o	ther constan	ts for		
3.	Tidal differ	Tences and o	ther constan	ts for		
3.	Tidal differ	(positio	n) HEI	ts for /	(place	
3.	Tidal differ Lat: • TI (Hour,	(positio ME Minute)	n) HEI (Fe	ts for/	(place	RATIO
3.	Tidal differ Lat: • TI (Hour,	(positio	n) HEI (Fe	ts for/	(place	RATIO
3.	Tidal differ Lat: • TI (Hour,	(positio ME Minute)	n) HEI (Fe	ts for/	(place	RATIO
	Tidal differ Lat: • TI (Hour,	(positio ME Minute) Low Water	n) HEI (Fe High Water	ts for ////// GHT et) Low Water	(place	RATIO
	Tidal differ Lat: (Hour, High Water	(positio ME Minute) Low Water sh smooth t	n) HEI (Fe High Water	ts for	(place HEIGHT (If App High Water	RATIO licable) Low Water
	Tidal differ Lat: (Hour, High Water	(positio ME Minute) Low Water sh smooth to	n) HEI (Fe High Water	ts for	(place (place HEIGHT (If App High Water	RATIO licable) Low Water dian)
	Tidal differ Lat: (Hour, High Water Please furni in the follo	(positio ME Minute) Low Water sh smooth t. wing units: one)	n) HEI (Fe High Water ide correcti	ts for	(place HEIGHT (If App High Water (Time Merical)	RATIO licable) Low Water dian)
	Tidal differ Lat: (Hour, High Water Please furni in the follo (check	(positio ME Minute) Low Water sh smooth t. wing units: one)	n) HEI (Fe High Water ide correcti	ts for	(place HEIGHT (If App High Water (Time Merical) (Check one	RATIO licable) Low Water dian) t interval:

11/28/73

U. S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY

TIDE NOTE FOR HYDROGRAPHIC SHEET

Processing Division: Atlantic Marine Center

Hourly heights are approved for

Tide Station Used (NOAA form 77-12): Galveston Pleasure Pier

Period: June-July 1973

HYDROGRAPHIC SHEET:

OPR: 479

Locality: Offshore, Galveston, Texas

Plane of reference (mean lower low water): 2.5 feet which is feet on tide staff.

Height of Mean High Water above Plane of Reference is 2.1 feet

Remarks:

Zoning	Time Difference	Lat.	Long.
Area 1	-1.0 hr.	29°09'n	94°23'W
Area 2	-1.5 hr.	-/429"03n	94°11'W
Area 3	-1.8 hr.	28°56'n	94°01'W
Area 4	-1.3 hr.	28°55'n	94°25'W

Chief, Tides Branch

•	ELECTRONIC CONTRO	L PARAMETERS	
1. Project # OPR- 479	2. Reg. # <u>H-</u>	3. Field # AH 40 - 3 - 72,	
4. Type of Control	RAYDIST	(Hi-Pix, Raydist, EPI, etc.)	_
5. Frequency	(for convers	ion of electronic lanes to meters	3)
6. Mode of Operation	(check one):		
Range-Range 🔀		Range-Visual	
Range One (R_1) Station I.D. Range Two (R_2) Station I.D.	MANT 1973	Lat. 29 ° 40 ' 30.7156 ' Lat. 29 ° 14 ° 52 ' 54.716 ' 51.7156 ' 51	! !
Hyperbolic (3-sta	ation)	Hyper-Visual	
Slave One Station I.D. Master Station I.D. Slave Two Station I.D.		Lat. Long. Lat. Long. Lat. Long. Lat. Long.	
7. Location of Survey:			Ψ,
Range-Range	Imagine an obser looking directly	ver is standing at R_1 Station and at R_2 (check one):	i
	Survey area is	to observer's Right A=Ø	
,	Survey area is	to observer's Left 🔀 A=1	
Hyperbolic	Looking from sur	vey area toward Master Station:	

MILITARITY OF THE CHARLES

Slave Two must be to observer's Right.

8. This form is submitted as an aid in preparing a boat sheet.

This form applies to all data on this survey.

This form applies to part of the data on this survey.

Vessel	From	То	Position Numbers
ED1	Time Day	Time Day	(inclusive)
			to
	The state of the s		to

Slave One must be to observer's Left.

9. Remarks: MAKE R. ARCS Red ; R. ARCS BLUE

ATLANTIC MARINE CENTER

PROJECTION PARAMETERS

POLYCONIC OR MODIFIED TRANSVERSE MERCATOR

1. Project No. OPR 479 4. Requested By CO. Ruda Heek Tran AMC
2. Reg. No 5. Ship or Office Rude / Heck
3. Field No. 41 40-2-73 6. Date Required 471 1973
7. Polyconic Modified Transverse Mercator
8. Central Meridian of Projection 93 . 56 1 00 w
9. Survey Scale: 1: 40,000
10. Size of Sheet (check one):
36 x 54 36 x 60 Other Specify 42 x 54
11. Sheet Orientation (check one):
NYX = 1
N
N.
CMER CMER
12. Plotter Origin W. Corner of Charles
12. Plotter Origin: S.W. Corner of Sheet (not necessarily a grid Latitude 28 ° 4/ ' 70 " intersection)
I ongitude All o
13. G.P.'s of triangulation and/or signals attached.
14 Material party
14. Material Desired: Tracing Paper Mylar Mylar
Smooth Sheet Other Specify
LONDITION - REQUEST LONGITUDE VALUES BE DEWITED OUT ALONG CENTRAL
LATTITUDE (28.82) IN Addition To Top & BOTTOM of BEATSHEET
) 3 ' 5 6 '

NOAA FORM 76-155 (11-72)	NATIONAL (DCEANIC		EPARTME OSPHERIC			SU	RVEY N	JMBER		
	GEOGRAPH		H-9300 WD								
Name on Survey	A ON CHART HO CON U.S. MAPS ON LOCAL MAPS ON										
										1	
										2	
										3	
										4	
								Ì		Ŀ	

Time (Hours)

Time (Hours)

Time (Hours)

Quality Control Inspection by

Requirements Evaluation by

03/29/78

Dete

Date

Date

ATLANTIC MARINE CENTER VERIFIER'S REPORT/ADDENDUM TO THE DESCRIPTIVE REPORT

REGISTRY NO. H-9300 WD

FIELD NO. R/H-40-2-73

Gulf of Mexico, Texas, Galveston Safety Fairways

SURVEYED: June 11 through June 22, 1973

SCALE: 1:40,000 PROJECT NO.: OPR-479

SOUNDINGS: Wire Drag CONTROL: Raydist

(Range-Range)

Chief of Party L. E. Pickens Surveyed by Ship's Personnel

Automated Plot of Preliminary

September 2, 1977

1. Introduction

The concern of this survey is to clear a portion of the Safety Approach Fairway to Galveston Bay, Texas. The general boundaries are from latitude 28° 55'N to 29° 03'N and longitude 94° 01'W to 94° 11'W.

2. Control and Shoreline

- The control is adequately described in the Descriptive Raydist in the Range-Range mode was used for position control throughout the survey.
 - There is no shoreline on this survey.

Condition of the Survey

Field Work

The field work is satisfactory, except as noted on the wiredrag tests in Section 9 of this report.

b. Records

The records are complete and comprehensive for this survey, with the exception of the tender tester records which were poor.

c. Descriptive Report

The Descriptive Report is complete and comprehensive, except as noted below.

- (1) Three separate, registered surveys are included under this one Descriptive Report. It is difficult and confusing to separate the report data into the individual surveys as much of the data was not noted to which survey or surveys were applicable.
- (2) The listing of hangs and groundings is incomplete and inaccurate. Appendix I of this report replaces this data for this survey.
- (3) Although there were no Presurvey Review items on this survey, a statement to that effect should have been made in the Descriptive Report.
 - (4) Junctional surveys were not listed.
- (5) Neither charts used for comparison nor individual discrepancies were listed.
- (6) The data contained in Attachments II, III, and IV are not separated for each survey.

d. Field Plotting

Field plotting was not satisfactory.

- (1) The field plotted each strip on individual mylar overlays but failed to transfer these strips to the boat sheet.
- (2) The field A & D Sheet was not constructed in accordance with the Wire Drag Manual (i.e. no colors, no marginal notes, none or improper symbols, etc.).
- (3) The boat sheet did not cover the entire survey area.

e. Office Plotting (Smooth)

The survey was accurately and neatly smooth plotted in accordance with instructions outlined in the letter of Richard H. Houlder, Associate Director, Office of Marine Surveys and Maps; dated February 23, 1977; titled "Processing Wire Drag Surveys on Safety Fairways".

4. Junctions

This survey junctions with H-9342 WD (1973), R/H-40-2-72 on the northwest. This junction has not been accomplished, as this junctional survey has not been processed and it is expected to be several months before processing is started.

5. Comparison With Hydrographic Surveys

Comparison with hydrographic surveys was not accomplished during verification.

6. Comparison With Charts 11332 (14th Edition, February 12, 1977)
11340 (35th Edition, April 16, 1977)
11300 (19th Edition, October 23, 1976)

a. Hydrography

Except as listed below, there is no conflict between wire-drag effective depths and the charted soundings. However, harmony between the survey and chart cannot be claimed due to the numerous conflicts and insufficient bottom clearances in areas not in conflict. See Section 8 of this report for recommendations.

- (1) The charted sounding of 51 feet, located at latitude 28° 59' 44", longitude 94° 05' 29", was cleared by an effective depth of 59 feet.
- (2) The charted sounding of 50 feet, located at latitude 28° 59' 32", longitude 94° 06' 12", was cleared by an effective depth of 51 feet.
- (3) The charted sounding of 47 feet, located at latitude 28° 59' 26", longitude 94° 05' 54", was cleared by an effective depth of 51 feet.
- (4) The charted sounding of 54 feet, located latitude 28° 58' 48", longitude 94° 05' 54", was cleared by an effective depth of 57 feet.
- (5) The charted sounding of 55 feet, located at latitude 28° 58' 46", longitude 94° 05' 35", was cleared by an effective depth of 57 feet.
- (6) The charted sounding of 54 feet, located at latitude 28° 58' 26", longitude 94° 05' 35", was cleared by an effective depth of 57 feet.

H-9300 WD

(7) The charted sounding of 53 feet, located at latitude 28° 57' 56", longitude 94° 05' 33", was cleared by an effective depth of 58 feet.

- (8) The charted sounding of 54 feet, located at latitude 28° 58' 30", longitude 94° 05' 10", was cleared by an effective depth of 57 feet.
- (9) The charted sounding of 56 feet, located at latitude 28° 58' 23", longitude 94° 04' 53", was cleared by an effective depth of 57 feet.
- (10) The charted sounding of 57 feet, located at latitude 28° 58' 37", longitude 94° 04' 33", was cleared by an effective depth of 59 feet.
- (11) The charted sounding of 56 feet, located at latitude 28° 58' 18", longitude 94° 04' 30", was cleared by an effective depth of 57 feet.
- (12) The charted sounding of 58 feet, located at latitude 28° 58' 15", longitude 94° 04' 08", was cleared by an effective depth of 59 feet.
- (13) The charted sounding of 58 feet, located at latitude 28° 58' 17", longitude 94° 03' 30", was cleared by an effective depth of 59 feet.
- (14) The charted sounding of 58 feet, located at latitude 28° 58' 02", longitude 94° 03' 08", was cleared by an effective depth of 59 feet.
- (15) The charted sounding of 57 feet, located at latitude 28° 57' 34", longitude 94° 02' 06", was cleared by an effective depth of 58 feet.
- (16) The charted sounding of 57 feet, located at latitude 28° 57' 02", longitude 94° 02' 28", was cleared by an effective depth of 59 feet.
- (17) The charted sounding of 54 feet, located at latitude 28° 57' 02", longitude 94° 01' 26", was cleared by an effective depth of 57 feet.

b. Aids to Navigation

No aids to navigation were located by this survey.

7. Compliance With Project Instructions

Except as noted below, the survey adequately complies with the project instructions OPR-479-RU/HE-73.

- a. Buoy groundings and their clearances were not within the required limits and were not listed, reference Section 2.12 of the project instructions.
- b. Survey effective depths generally do not comply with bottom clearance specifications, reference Section 2.14 of the project instructions.
- c. As stated in Sections K and L of the Descriptive Report, ship reconnaissance hydrography was conducted. However, no record of any hydrography was included in the survey records. Reference Section 2.17 of the project instructions.

8. Additional Field Work

Due to the discrepancies and differences between the survey and the chart, it is recommended that this area be resurveyed by both hydrography and wire drag. Due to the poor tests this survey can only be considered as supplemental. (See Section 9b of this report.)

9. Miscellaneous


- a. There are no splits within the survey.
- b. Testing of the wire drag was grossly inadequate. Often sections were not tested during a drag or once a good (low lift) test was obtained the section was never retested. Generally only one, occasionally two tests were performed per section per drag. Almost all tests throughout the survey were "Tester on Bottom" (TOB) tests. Due to this crucial inadequacy of the tests, this survey can only be, at best, considered supplemental.
- c. There were ten wire drag strips run on this survey; none were rejected and all strips were used in smooth plotting.
- d. It was necessary to plot all strips on rough plotting overlays so that each strip could be properly evaluated. The rough overlays contain notes of the smooth plotter/verifier listing the problems encountered and the disposition of these problems. Other notes, comments, corrections, and evaluations may be found in the survey's volumes and in the Descriptive Report.

- e. The ten wire drag strips plotted on the smooth sheets cover four buoy groundings with maximum clearances of these groundings. There were no hangs on this survey.
- f. The plotting of individual strips was aided by the automated plot of both vessels' positions, the "N" and the "F" buoys' positions, and latitude and longitude grid ticks. The projections, control arcs, distortion points, and stamp on the smooth position number/contron overlay and the smooth A & D Sheet were also automated plots. All other work was accomplished manually.
- g. This survey has been processed in accordance with the letter referenced in paragraph 3e of this report. With the aforementioned exceptions, modifications, and recommendations, this survey is considered complete and no further processing is planned.
- h. The smooth tides listed in the Descriptive Report were not used. Those tides were computed for Area One and none of the four tide zones are defined in either the Descriptive Report or the project instructions. Therefore, smooth tides were recomputed using a time difference of -1.4 hours which is an average of the four zoning areas. This is considered satisfactory due to the height of mean high water (MHW) above datum being only 2.1 feet and the interval for wire drag being 0.5 feet. These new smooth tides will apply to all three surveys (H-9300 WD, H-9341 WD, and H-9342 WD).

RATRAUSALL

H-9300 W.D. R/N-40-2-73
Abstract of Groundings
Addendum Appendix = I

er.					_						
Hang (4) Grounding	Strip No.	Pasition No.	Section Busy No.	Latitude	Longitude	Hang Grounding Eff. Depth	Clearing Strip	Cleared Eff. Depth	Charted Depth	Direction of Strip	Remarks
G	D-1	23D	'n	28 ⁸ 58 44	94°06 02	57 ′.			54	E	Area of conflict between short & survey
							E-2	57		NW	Clearing Strip
							- •-				
G	E-I	5E	, N,	28°58′51″	94 06 06	58 [']	•		54	மகம	Area of conflict between chart's survey
!			:				E-2	57 [']	•		Clearing Strip
; ;											
G	E-2	25 E	"N"	28°58'40"	94 06 21	57		·	55 '	Nω	Area of conflict between chart & survey
						,	D-1	52 [']			Clearing Strip
					·		,				
G	E-2	275	"F"	29.00 04	94°05′45″	5 <i>9</i> ′			<i>55</i> ′	שא	Area of confict between chart & survey
!							E-1	5 <i>5</i> ′		1	Clearing Strip.
			;	1	*		٠.				
t .		1 1					1			1	
1			•								•
			. • .							-	
	·										
		•								-	
		•									
!											
										-	
		4									



NAUTICAL CHART DIVISION

RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. 9300 WD

INSTRUCTIONS

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

1. Letter all information.

2. In "Remarks" column cross out words that do not apply.

3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

CHART	DATE	CARTOGRAPHER	REMARKS
11332	4-6-78	J. OWYANG	Full Part Before After Verification Review Inspection Signed Via
11300	70.0	7.007	Drawing No. 21 NO CORRECTION, INADEQUATE SURVEY
112/16	10 22 24		Dill D. D. C. At. M. W. C. D. L. C. L. C. L. C.
1/140	10-23-18	J. OWYANG	Full Part Before After Verification Review Inspection Signed Via Drawing No. 56 No CORRECTION, MARKAUATE SURVEY
411	5/31/79	J. OWYANG	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. 54 NO CORRECTION.
//332	10-1-79	D 20 Pakin	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. 23 CATEGORY 1 SURVEY CONSIDERED
11300	10.1.70	DMPapin	Full Pare Before After Verification Review Inspection Signed Via
71300	10-171	<i>Myrapus</i>	Drawing No. 37 CATEGORY 1 SURVEY CONSIDERED
			ADEQUATELY APPLIED
411	10-1-79	Da Papin	Full Pare Before After Verification Review Inspection Signed Via
			Drawing No. 55 CATEGORY 1 SURVEY CONSIDERS
- Kale -			ADEQUATELY APPLIED
11340	10-1-79	D21 Perkin	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. 58 CATEGORY 1 SURVEY CONSIDER
<u> </u>	· · · · · · · · · · · · · · · · · · ·		ADEQUATELY APPLIED
			Full Part Before After Verification Review Inspection Signed Via Drawing No.
			Drawing No.
	•		Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.